


CONCRETE BATCHING PLANT



TES – Distributor of **SIMEM batching plants** and **Precast Systems** in Australia and New Zealand

TES/SIMEM Supporting the construction industry with Quality products and Global experience through:

- Concept design
- Mechanical Engineering
- Fabrication of all equipment
- Commissioning
- Onsite training
- Site Support

PROJECT

Mansfield Premix
Mansfield, Victoria

Plant model
ZINGO DOS + 2 x 85m³ silos

Plant description

MOBILE DRY batching plant with wheel loader aggregates dosing, minimal foundations required, (or NO foundations option available) designed to reduce erection and disassembling works.

Plant includes:

- aggregates weighing hoppers with wheel loader dosing
- supporting frame
- cement and water manual dosing devices
- manual system to load truck mixer

Plant capacity

Plant is designed to **batch up to 7.6 m³/cycle** of standard concrete in continuous production; overall capacity might be affected by limited receiving capacity of truck mixers. Production up to **60 m³** per hours.



If your looking for a Batch Plant or precast plant solutions, please give us a call at TES

PHONE: 1300 300 375

transporteng.com.au info@transporteng.com.au



MELBOURNE • SYDNEY • BRISBANE • PERTH • ADELAIDE